

## BLOOMINGDALE FIRE PROTECTION DISTRICT ALARM MONITORING PROTOCOL

This system shall be installed by a licensed fire alarm contractor per Illinois State law and a copy of their license shall be submitted to the Fire Prevention Bureau prior to installation. 225 ILCS 447

A copy of the UL listing or approved agency certification for this monitoring shall be submitted to the Fire Prevention Bureau along with current contract for said service. NFPA 72 2007 Ed, 8.3.5.

Monitoring equipment specification sheets shall be submitted prior to installation. IFC 901.2

All fire alarm control equipment shall have sixty (60) hours of standby and five (5) minutes of alarm current for secondary power battery standby. Bloomingdale 907.1.2.1.

Any permits required by local city, village or county and must be obtained prior to installation. It is the responsibility of the fire alarm contract to call the jurisdiction for permit verification.

Upon completion of installation, the system shall be tested by the fire alarm contractor and shall provide the Fire Prevention Bureau with a copy of the installation report.

Upon completion of testing, a report including fire, trouble and supervisory and fail to test signals received at the supervising station, and the number or radio paths and signal strengths used shall be submitted via e-mail to [garyk@bloomingtonfire.com](mailto:garyk@bloomingtonfire.com). NFPA 72 2007 Ed. 8.3.8.3, 8.5.5.1.

The fire alarm monitoring service shall report all fire alarm and related signals to this emergency number (630) 690-8245.

Please review Bloomingdale Fire Protection District Ordinance 14-292 Minimum Fire Protection Regulations for acceptable communications.